Addendum No. 1

July 10, 2013

2013 Citywide Sidewalk Repair Project

Following changes to the contract

1) GENERAL CONDITIONS

Currently Section 5.3.6 of the General Conditions states:

> 5.3.6. The parties hereto understand and agree that CITY is relying on, and does not waive or intend to waive by any provision of this Agreement, the monetary limitations (presently $150,000 per person and $600,000 per occurrence) or any other rights, immunities, and protections provided by the Colorado Governmental Immunity Act, § 24-10-101 et seq., C.R.S., as from time to time amended, or otherwise available to CITY, its officers or its employees.

This section has been modified in the Supplementary Conditions to read:

> 5.3.6. The parties hereto understand and agree that CITY is relying on, and does not waive or intend to waive by any provision of this Agreement, the monetary limitations (effective July 1, 2013, $350,000 per person and $990,000 per occurrence) or any other rights, immunities, and protections provided by the Colorado Governmental Immunity Act, § 24-10-101 et seq., C.R.S., as from time to time amended, or otherwise available to CITY, its officers or its employees.

2) SPECIAL PROVISIONS

Currently paragraph 2 of Section 1.7 of the Special Provisions states:

Curb ramp and detectable warning must comply with all ADA regulations. All curb ramps and wings shall have a maximum slope of 12:1 in any direction. Detectable Warning Material on the new curb ramps shall be USA Safety Domes Wet Set Mounts, brick red in color, and cast-in-place according to product specifications. Reference **Construction Drawings 4-5** for curb ramp details.

This paragraph has been modified to read:

Curb ramp and detectable warning must comply with all ADA and DOT regulations. Curb ramp and wings shall have a maximum slope of 12:1 in any direction. Detectable warning shall be cast iron or approved equal by Engineer, Brick Red in color, and cast-in-place according to product specifications. Detectable warning shall measure a minimum of four feet (4') in width and two feet (2') in depth and shall be set back from the flow line a minimum of six inches (6") but no more than eight inches (8") at all points. Reference **Construction Drawings 4-5** for curb ramp details.

END OF ADDENDUM

ATTACHMENTS

SUPPLEMENTARY CONDITIONS-Addendum No. 1
SC-1 to SC-6

SPECIAL PROVISIONS- Addendum No. 1
SP-1 to SP-9