



## Addendum No. 1

**To:** All Bidders  
**From:** Matt Knight, P.E., City Engineer  
**Date:** August 5, 2019  
**Subject:** Addendum No. 1

The Bid Documents, previously prepared and issued for the above Project, are hereby modified as herein below described. Bidders shall acknowledge receipt of this Addendum, by number, in the space provided on the Contractor's Bid form.

### **BID DOCUMENTS:**

The Contractor's Bid Form and Segment Breakdown Spreadsheet for this project were updated. A revised Contractor's Bid Form is attached to this addendum. This Contractor's Bid Form shall be the one used and submitted with the rest of the bid documents.

### **QUESTIONS:**

The following questions were provided. The answers to the questions provided are shown in bold.

1. There is a specification for fabric application but there is no bid item for it or no mention of it on the bid sheet. Do you want fabric applied to any of these streets?

**We do not anticipate having to use fabric this year and did not include it in our bid items but have included the fabric application specifications as a reference if needed.**

2. Typically residential streets are chip sealed with ¼" chips on the surface which has a much higher public acceptance and appreciation response. Would the City consider alternate pricing for ¼" chips on the surface of both areas?

**The City generally uses 3/8" chips for our residential streets and have been happy with the way it performs on pavement with low PCI scores. With this, the City is not interested in considering alternative pricing for ¼" chips.**

3. Can the contractor completely close each parking lot during the slurry seal process?

**No, unfortunately we are unable to close down the Police Department lot or the Library lot.**

4. What parking areas are to be slurry sealed in the Police Station/Fire Station areas? The total areas of both lots is closer to 9,000 SY.

**All the parking areas front to back will need to be sealed at the Police department and only the northern parking lot at the Fire Station, including the entire driveway between the two (2) departments. The total square yardage was not shown correctly on the Contractor's Bid Form or the Segment Breakdown Spreadsheet. Those documents have been updated and included in this addendum. Please use these updated sheets with the bid submission. Incorrect documents submitted as part of the bid submission will result in submitted bid being disqualified.**

5. It sounds like the City plans for the contractor to cover the thermoplastic pavement markings prior to chip seal work and then uncover the markings and touch them up with paint afterward. Is that what the City is requesting in this bid or do you want new thermoplastic markings? To the best of our knowledge epoxy pavement markings are not applied to do touchups to thermoplastic.

**All thermoplastic marking should be covered at time of sealing. We do not anticipate touchups to the pavement markings as part of this project.**

6. If the City wants new thermoplastic markings the existing markings will need to be removed prior to chip seal work. A note to that effect would be good.


**No replacement of thermoplastic markings are required as part of this project.**

7. I see 84 square feet of thermoplastic markings on Lucerne Drive and 250 square feet on Excalibur Street. Are those the correct totals and are there any other locations on this project that the City has thermoplastic markings?

**It is the contractor's responsibility to determine location where pavement markings need to be covered as part of this project. We do not provide this information as part of the bid package.**

8. I see approximately 1,900 lineal feet of double yellow centerline markings of Lucerne Drive. Are there any other long line markings on these streets that the City wants applied?

**No.**



---

Matt Knight, P.E.  
City Engineer

Project: 2019 Street Surface Restoration Project  
Contractor:  
Design Professional: City of Lafayette  
Total Cost:  
Term:  
Acct. or P.O. #



**CONTRACTOR’S BID – ADDENDUM #1**

**I.** The following Proposal is hereby made to:  
City of Lafayette  
1290 S. Public Road  
Lafayette, Colorado 80026

**II. STIPULATED AMOUNT**

The undersigned hereby propose and agree to furnish all the necessary labor, material, equipment, tools, and services necessary for the construction of the **2019 Street Surface Restoration Project** for the City of Lafayette all in accordance with the Contract Documents prepared by the City of Lafayette Department of Public Works for the following stipulated amount: \_\_\_\_\_  
\_\_\_\_\_ Dollars and \_\_\_\_\_ Cents ( \$ \_\_\_\_\_ ), based on unit prices.

**III. KNOWLEDGE OF LOCAL CONDITIONS AND CONTRACT DOCUMENTS**

The undersigned has examined the location of the proposed work, as well as Contract Documents and is familiar with the local conditions present where the work is to be performed.

**IV. PROPOSAL GUARANTY**

The Proposal Guaranty attached, without endorsement, in the sum of not less than five percent (5%) of the amount of the Proposal, is furnished to the OWNER as a guarantee that the Agreement will be executed and a Performance Bond and a Payment Bond will be furnished within five(5) Business Days after award of the Contract to the undersigned, or that the undersigned will pay to the OWNER the difference between the stipulated amount of this Contractor’s Bid and such larger amount for which the OWNER may in good faith contract with another party to perform the work covered by this Proposal, provided that such payment shall be limited to the amount of the Proposal Guaranty.

**V. EXECUTION OF AGREEMENT AND FURNISHING BONDS**

Within five (5) Business Days after being awarded the Contract, the undersigned agrees to execute the form of Agreement included in Contract Documents, and to furnish a Performance Bond and Payment Bond, both in an amount equal to one hundred percent (100%) of the Contract amount on the forms provided in these documents.

**VI. ADDENDA**

The undersigned hereby acknowledges receipt of the following Addenda:

| Addendum No. | Dated |
|--------------|-------|
| _____        | _____ |
| _____        | _____ |
| _____        | _____ |
| _____        | _____ |

## VII.STATEMENT OF ITEMS

| <u>Item</u><br><u>No.</u>                            | <u>Description, Approximate Quantity and Unit Price</u> | <u>Amount of Bid</u> |
|--|---|----------------------|
| <b>1. MOBILIZATION</b>                               |   |                      |
|  | _____   | = \$ _____           |
|  | (Words – Lump Sum Price)                                | (Total)              |
| <b>2. TRAFFIC CONTROL</b>                            |   |                      |
| 6  | DAYS x \$ _____ / DAY                                   | = \$ _____           |
|  | _____   | (Total)              |
|  | (Words – Unit Price)                                    |                      |
| <b>3. STRIPING AND PAVEMENT MARKING</b>              |   |                      |
|  | _____   | = \$ _____           |
|  | (Words – Lump Sum Price)                                | (Total)              |
| <b>4. CHIP SEAL (3/8”) WITH FOG COAT</b>             |   |                      |
| 1,210  | SY x \$ _____ / SY                                      | = \$ _____           |
|  | _____   | (Total)              |
|  | (Words – Unit Price)                                    |                      |
| <b>5. DOUBLE CHIP SEAL (3/8”,3/8”) WITH FOG COAT</b> |   |                      |
| 7,584  | SY x \$ _____ / SY                                      | = \$ _____           |
|  | _____   | (Total)              |
|  | (Words – Unit Price)                                    |                      |
| <b>6. SLURRY SEAL (INCLUDES CITY PARKING LOTS)</b>   |   |                      |
| 38,130   | SY x \$ _____ / SY                                      | = \$ _____           |
|  | _____   | (Total)              |
|  | (Words – Unit Price)                                    |                      |
| <b>TOTAL PRICE \$ _____ WORDS _____</b>              |   |                      |

**VIII.CONTRACT TIME**

All work shall be completed by within sixty (60) calendar days after the issuance of the Notice to Proceed. The OWNER anticipates issuance of the Notice to Proceed within fourteen (14) calendar days from the date of the Notice of Award.

Furthermore, the Bidder agrees that failure to complete the Contract within the time proposed, including any extension thereof, shall be considered a breach of the Contract, and entitles the OWNER to liquidated damages as specified in Article 3 of the Construction Contract.

**IX.OWNER'S RIGHT RESERVED**

The undersigned understands that the OWNER reserves the right to reject any or all Proposals and to waive any formality or technicality in any Proposal in the interest of the OWNER.

**THE ABOVE PROPOSAL IS HEREBY RESPECTFULLY SUBMITTED BY:**

CONTRACTOR

Business Name\_\_\_\_\_

an individual,  a Colorado corporation,  a Colorado partnership,  a Colorado limited liability company,  a \_\_\_\_\_, as independent contractor.

Business Address\_\_\_\_\_

City\_\_\_\_\_ State\_\_\_\_\_ Zip Code\_\_\_\_\_

By\_\_\_\_\_ Title\_\_\_\_\_

Date\_\_\_\_\_

# Addendum #1

## 2019 CITY OF LAFAYETTE STREET SURFACE RESTORATION



| Type                         | Location          | Start Point             | End Point                | Estimated     | Unit      | Notes   |
|------------------------------|-------------------|-------------------------|--------------------------|---------------|-----------|---|
| <b>Centaur Village Drive</b> |                   |                         |                          |               |           |   |
| Slurry Seal                  | Forum St.         | Caria Dr                | Atlantis Ave             | 1,977         | SY        |   |
| Slurry Seal                  | Acropolis Dr      | Atlantis Ave            | Centaur Village Dr       | 2,490         | SY        |   |
| Slurry Seal                  | Apollo Dr         | Atlantis Ave            | Acropolis Dr             | 1,981         | SY        |   |
| Slurry Seal                  | Neptune Dr        | Atlantis Ave            | Acropolis Dr             | 1,763         | SY        |   |
| Slurry Seal                  | Scorpius Dr       | Neptune Dr              | CDS                      | 1,333         | SY        |   |
| Slurry Seal                  | Olympian Cir      | Atlantis Ave            | CDS                      | 1,616         | SY        |   |
| Slurry Seal                  | Atlas Cir         | Forum St                | CDS                      | 1,010         | SY        |   |
| Slurry Seal                  | Atlantis Ave      | Caria Dr                | S. Boulder Rd            | 7,309         | SY        | 1 Crosswalk   |
| Slurry Seal                  | Cressidia Ct      | Caria Dr                | CDS                      | 1,909         | SY        |   |
|                              |                   |                         | <b>Total</b>             | <b>21,388</b> | <b>SY</b> |   |
| <b>South Point</b>           |                   |                         |                          |               |           |   |
| Slurry Seal                  | Hawk Ct           | Hawk Ct                 | End                      | 1,103         | SY        |   |
| Slurry Seal                  | Black Bear        | Black Bear              | End                      | 800           | SY        |   |
| Slurry Seal                  | Falcon Pt         | Falcon Ptparking stalls | End                      | 1,502         | SY        |   |
| Slurry Seal                  | Racoon Ct         | Racoon Ct               | End                      | 815           | SY        |   |
|                              |                   |                         | <b>Total</b>             | <b>4,220</b>  | <b>SY</b> |   |
| <b>City Facilities</b>       |                   |                         |                          |               |           |   |
| Slurry Seal                  | Police Department |                         |                          | 6,649         | SY        | Parking stalls, 1 crosswalk, 1 stop bar, 3 ADA Parking stalls |
| Slurry Seal                  | Fire House #1     |                         |                          | 1,066         | SY        | Parking stalls, 2 ADA parking stalls                          |
| Slurry Seal                  | Senior Center     |                         |                          | 641           | SY        | Parking Stalls, 4 ADA parking stalls                          |
| Slurry Seal                  | Library           |                         |                          | 4,166         | SY        | Parking Stalls, directional arrows, 4 ADA parking stalls      |
|                              |                   |                         | <b>Total</b>             | <b>12,522</b> | <b>SY</b> |   |
|                              |                   |                         | <b>Slurry Seal Total</b> | <b>38,130</b> | <b>SY</b> |   |
| <b>W Lucerne Drive</b>       |                   |                         |                          |               |           |   |
| Double Chip                  | W Lucerne Dr      | HWY 287                 | Beacon Hill              | 7,584         | SY        | Center Lane Line, 2 crosswalks                                |
|                              |                   |                         | <b>Total</b>             | <b>7,584</b>  | <b>SY</b> |   |
|                              |                   |                         | <b>Double Chip Total</b> | <b>7,584</b>  | <b>SY</b> |   |
| <b>Excalibur Street</b>      |                   |                         |                          |               |           |   |
| Single Chip                  | Excalibur St      | Malory St               | Modred Dr                | 1,210         | SY        | 1 stop bar, 1 crosswalk                                       |
|                              |                   |                         | <b>Total</b>             | <b>1,210</b>  | <b>SY</b> |   |
|                              |                   |                         | <b>Single Chip Total</b> | <b>1,210</b>  | <b>SY</b> |   |